

# OREGON CORNER RESTORATION FORM

SECTION 33, 34 TOWNSHIP 5 NORTH RANGE 29 EAST  
COUNTY : UMATILLA DATE DEC/22

Z-13

CORNER DESIGNATION  
SECTION CORNER

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNCOVERED  
 SURVEYED IN  
 REFERENCED

PREVIOUS RENEWALS / SURVEYS, ETC.



SURVEYED IN 1860 BY MAXON AND HURD UNDER CONTRACT #50, THEY SET POST AND MADE MOUND.  
IN 1990 LS 951 SET A 2 1/2" BRASS CAP IN CONCRETE OVER 1 1/4" IRON PIPE OF UNKNOWN ORIGIN.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

FOUND 2 1/2" BRASS CAP STAMPED AS BELOW.  
FOUND ALUMINUM TAG IN RAIL ROAD TIE STAMPED LS 951 BEARS N 59° E, 1.10'.  
FOUND ALUMINUM TAG IN RAIL ROAD TIE STAMPED LS 951 BEARS N 88°44'26" E, 57.86'.  
FOUND 2 1/2" BRASS CAP STAMPED AS BELOW BEARS N 00°00'08" W, 12.00'.  
FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP STAMPED LS 951 BEARS N 00°53'40" E, 107.66'.

MONUMENT DETAIL

2 1/2" BRASS CAP WC



NAD 83/91  
OREGON STATE PLANE  
INTERNATIONAL FEET

803962.49  
8537802.61

MONUMENT SET ( PROCEDURES AND DESCRIPTION )

NEW ACCESSORIES FROM WHICH

LOCATION AND COMMENTS

CORNER FALLS NEAR A FENCE  
CORNER ON THE SOUTHERLY  
PROJECTION OF TABOR ROAD AND  
THE EASTERLY PROJECTION OF  
PUNKIN CENTER ROAD.

FIRM/AGENCY

PRIMM LAND SURVEYING, INC.  
P.O. BOX 1322  
HERMISTON, OREGON 97838

LAND SURVEYOR

BRIT L. PRIMM

WITNESS

KEITH P. PRIMM

SURVEYOR'S SEAL

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 13, 1999  
BRIT L. PRIMM  
48509

EXPIRATION DATE: 12/31/24