

OREGON CORNER RESTORATION FORM

SECTION:36 TOWNSHIP: 5N RANGE: 29E Z-23

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

S1/4 Section 36

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Maxon & Hurd under Contract # 50 in 1860. They set post and made mound.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Nothing found.

MONUMENT DETAIL

SC
T5NR29E
1/4 36
2005
951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

804147.95
8551003.11

MONUMENT SET (PROCEDURES AND DESCRIPTION)

Set a 1"x30" iron pipe in concrete with a 2 3/8" brass cap flush with the ground stamped as above. An old fence corner (north and east) lies 3' West of corner.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 47° 54' 56" W 54.13'
- A 4" U.S. BM brass cap bears S 89° 59' 47" E 117.79'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 89° 50' 07" E 790.93'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 86° 08' 36" E 443.63'

LOCATION AND COMMENTS

0.4 miles West of where the Highland extension to Cold Springs road turns East.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05