

OREGON CORNER RESTORATION FORM

SECTION:31 TOWNSHIP: 5N RANGE: 29E Z-3

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

S1/4 Section 31

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Maxon and Hurd under Contract # 50 in 1860. They set post and made mound. In 1910 survey # 306 Kimbrell set 2 1/2" iron pipe.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Found 2 1/2" iron pipe N 0° 16' 02" E 15.76'
(See monument set.)

MONUMENT DETAIL

T5NR29E
1/4 S31
2005
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

803794.23
8524518.28

MONUMENT SET (PROCEDURES AND DESCRIPTION)

Using Kimbrell's 2 1/2" iron pipe for Eastings and existing monuments on the standard parallel for Northings, I set a 5/8"x30" iron rebar with a 2" aluminum cap stamped as above flush with the pavement.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 37° 17' 08" E 34.59'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 0° 13' 56" W 28.82'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 59° 18' 51" W 36.97'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 21° 03' 49" E 36.47'


LOCATION AND COMMENTS

From the intersection of Ott road North with Punkin Center road, go East on Punkin Center 0.5 miles to corner.


SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH



G. Dennis Edwards



RENEWS 12/31/05