

OREGON CORNER RESTORATION FORM

SECTION:31 TOWNSHIP: 5N RANGE: 29E Z-5

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

SE Section 31

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Maxon & Hurd under Contract #50 in 1860. They set post and made mound.
 In 1906 GLO survey by Erickson found 3" iron pipe.
 In 1979 there was a brass screw and washer at this location.
 Roberts computed survey location in a 1997 survey for Holguin.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Nothing found.

MONUMENT DETAIL

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

803824.53
8527177.33

MONUMENT SET (PROCEDURES AND DESCRIPTION)

At the Easting location of Roberts corner and on a line between existing monuments on the standard parallel, I set a RR spike stamped 951 flush with the pavement. This location is also on the southerly projection of the north half of the east line of Section 31. This location also very nearly matches the 1906 GLO survey of section 32 by Erickson.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 18° 43' 42" E 92.82'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 36° 46' 01" W 41.57'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 75° 29' 46" W 119.45'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 24° 26' 01" E 32.89 (North corner of "Sather add".)

LOCATION AND COMMENTS

At the intersection of Craig road, Diagonal road, and Punkin Center road.

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH