

OREGON CORNER RESTORATION FORM

SECTION 31, 32 TOWNSHIP 5 NORTH RANGE 29 EAST
COUNTY : UMATILLA DATE DEC/22

Z-5

CORNER DESIGNATION
SECTION CORNER

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNCOVERED
 SURVEYED IN
 REFERENCED

PREVIOUS RENEWALS / SURVEYS, ETC.

SURVEYED IN 1860 BY MAXON AND HURD UNDER CONTRACT #50, THEY SET POST AND MADE MOUND.
IN 1906 GLO SURVEYOR ERICKSON FOUND 3" IRON PIPE.
IN 1979 LS 951 REPORTS BRASS SCREW AND WASHER.
IN 1997 ROBERTS COMPUTED LOCATION.
IN 2005 LS 951 SET A RAIL ROAD SPIKE.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

FOUND RAIL ROAD SPIKE.
FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP STAMPED LS 951 BEARS N 18°43'42" E, 92.82'.
FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP STAMPED LS 951 BEARS S 24°26'01" E, 32.89'.
FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP STAMPED LS 951 BEARS S 75°29'46" W, 119.45'.

MONUMENT DETAIL



NAD 83/91
OREGON STATE PLANE
INTERNATIONAL FEET

803824.66
8527177.49

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

SET 5/8" X 30" IRON ROD WITH YELLOW PLASTIC CAP STAMPED PLS LS 48509 BEARS N 37°57'39" W, 42.20'.

LOCATION AND COMMENTS

CORNER FALLS AT THE INTERSECTION
OF PUNKIN CENTER ROAD, CRAIG
ROAD AND DIAGONAL ROAD.

FIRM/AGENCY

PRIMM LAND SURVEYING, INC.
P.O. BOX 1322
HERMISTON, OREGON 97838

LAND SURVEYOR

BRIT L. PRIMM

WITNESS

KEITH P. PRIMM

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR



OREGON
JULY 13, 1999
BRIT L. PRIMM
48509

EXPIRATION DATE: 12/31/24

23-012-C