

OREGON CORNER RESTORATION FORM

SECTION:32 TOWNSHIP: 5N RANGE: 29E Z-7

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

S1/4 Section 32

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Maxon & Hurd under Contract # 50 in 1860. They set post and made mound.
In 1984 Edwards set 1/2" iron rebar over a 1" bolt.
In 1990 Edwards set a 2 1/2" brass cap in concrete over bolt.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Found 2 1/2" brass cap in concrete stamped as below flush with the pavement.
W.C. an alum. tag #951 in a RR tie fence post bears N 36° 04' 40" W 27.76' (27.94')
W.C. an alum. tag #951 in a power pole bears S 42° 40' 57" W 26.91' (26.89')

MONUMENT DETAIL

T5NR29E
S1/4
Sec 32
1990
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

803859.18
8529835.13

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 52° 21' 17" W 31.57'
A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 70° 48' 32" E 63.87'

LOCATION AND COMMENTS

At the intersection of Punkin Center road with Cabana road.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05