

OREGON CORNER RESTORATION FORM

SECTION:32 TOWNSHIP: 5N RANGE: 29E Z-9

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

SE Section 32

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Maxon & Hurd under Contract # 50 in 1860. They set post and made mound.
 In 1913 Kimbrell set 2 1/2" iron pipe.
 In 1975 Staebler drove 1/2" iron rebar into iron pipe.
 In 1990 Edwards set a 2 1/2" brass cap over 1/2" iron rebar.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Found 1/2" iron rebar 4" below the surface of a paved road.
 W.C. an aluminum tag # 951 in a RR tie bears N 23° 06' 31" W 67.62'(69.54')
 W.C. an aluminum tag # 951 in a power pole bears S 49° 30' 29" E 46.01'(45.96')
 W.C. an aluminum tag # 951 in a RR tie bears N 48° 25' 04" E 47.43'(47.26')

MONUMENT DETAIL

T5NR29E
 32 | 33
 1990
 L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

803893.83
 8532494.06

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 1° 23' 45" W 24.37'

LOCATION AND COMMENTS

At the intersection of Edwards road (North) with Punkin Center road.

SURVEYOR'S SEAL

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951

RENEWS 12/31/05

FIRM: EDWARDS SURVEYING LLC
 PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
 WITNESS: J. JOSEPH