

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/02/10

CORNER DESIGNATION: L-25, The East Quarter Corner of Section 13, Township 5 North, Range 33 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by Odell & Lewis under Contract No. 110 dated February 7th, 1865. Notes state: Set 1/4 Sec post corner on land descending to the North. Drove charred stake, dug pits, and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N
R33E R34E
1/4
S13 | S18
2010
PLS 1106

MONUMENT SET: Held the intersection of Duroc County Road with an old field berm extending west. This location is in conformance with the location of the corner calculated by Steve Haddock in his Survey No. 03-113-C. Set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 6" below ground road surface. Marked as shown in "Monument Marking Detail".

New Accessories:

A silver deep-1 magnet buried 18" below ground level in farmed field bears N 03° E, 32.2 feet.
An orange deep-1 magnet buried 18" below ground level in farmed field bears N 62° E, 26.9 feet.
A blue deep-1 magnet buried 18" below ground level in farmed field bears S 02° E, 25.3 feet.
A pink deep-1 magnet buried 18" below ground level in farmed field bears S 54° W, 25.6 feet.
Buried bearing object signs with all deep-1 magnet accessories.

LOCATION AND COMMENTS: Located in North-South gravel road, with edge of field berm extending West. It is noted that Duroc Road location moves east or west each time the adjacent fields are plowed. A steel tape and magnetic compass were used to measure bearings and distances to accessories.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 824601.71
E = 8680756.22


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells
Dean Roy

5N33L25



renews 6-30-12

RECEIVED BY
Umatilla County Surveyor
Date: 4/3/2012
Rec'd By: [Signature]
No.: 12-029-C