

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 07/02/10

CORNER DESIGNATION: N-25, The Southwest corner of Section 13, Township 5 North, Range 33 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by Odell & Lewis under Contract No. 110 dated February 7th, 1865. Notes state: Set post corner for secs 13, 24, 18 & 19, on level, Drove charred stake, dug pits, and raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None

MONUMENT MARKING DETAIL:

T5N
R33E | R34E
S13 | S18
S24 | S19
2010
PLS 1106

MONUMENT SET: Held the intersection of Duroc County Road extending West and Duroc County Roads extending North and South as best remaining evidence of original corner location. This location is in conformance with the location calculated by Steve Haddock on his Survey No. 03-313-C, with reference to old County Road Notes. Set a 2-3/8" diameter brass cap on a 1 1/4" x 30" galvanized iron pipe, with top of brass cap 14" below ground level and stamped as shown in "Monument Marking Detail".

New accessories:

- A 3" BPA Aluminum cap monument bears Grid Azimuth: 194°34'31", Grid Distance: 118.94 feet.
- A 5/8" by 24" rebar with 1 1/4" red plastic cap, 2" above ground level, bears S 35°W, 31.6 feet.
- A 3/4" diameter brass washer stamped "PLS 1106", 1 foot above ground level on power pole bears S 89°W, 110.0 feet.
- A 5/8" by 24" rebar with 1 1/4" red plastic cap, 2" above ground level, in road berm, bears N 03°W, 28.7 feet.

Nailed a "witness" sign, facing Southwest, to the power pole above the brass washer accessory.

Red plastic caps on rebar accessories are marked "OR PLS 1106 WA PLS 17372". The rebar accessories are set on road shoulder. Wired a bearing object sign to each of the rebar accessories.

LOCATION AND COMMENTS: Corner is located at a point in a currently farmed field where the projection of Duroc Roads to the North, South and West intersect. A steel tape and magnetic compass were used to measure bearings and distances to accessories.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:


N = 821924.18
E = 8680813.20

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801


COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells
Dean Roy



William R. Wells



renews 6-30-12

5N33N25

RECEIVED BY
Umatilla County Surveyor
Date: 4/3/2012
Rec'd By: [Signature]
No.: 12-029-c