

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/01/04

CORNER DESIGNATION: Z-17, The Standard Southeast Corner of Section 34, T5N., R33E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by William H. Odell and William L. Lewis, U.S. Deputy Surveyors under Contract No. 110, dated February 7, 1865. Record states: Set post, Standard Cor. for Secs. 34 and 35 on land gently sloping to the S., Drove charred stake, dug pits and raised mound as per instructions. Corner has been used in several County Road Surveys, although no description of recovered evidence is found in County Road Notes. A tie to this corner shows on 1888, Northern Pacific Railroad Maps, relative to the center of railroad track.

MONUMENT AND ACCESSORIES FOUND: None. The position of this corner was re-established based on ties to the location of the center of the old Northern Pacific Railroad track. See accompanying Survey Map. County Road Notes for County Roads 253 (1885), 254 (1885) and 291 (1887), all call for the center of the various County Roads to run through the corner. Corner position as reestablished by railroad ties puts the corner position 4 feet West of the current centerline of Kupers Road, which is acceptable and reasonable. Survey No. 99-299-B also positions the Southeast Corner of Section 34 from the railroad ties.

MONUMENT MARKING DETAIL:

S.C.
T5N R33E
S34 | S35
2004
PLS 1106

MONUMENT SET: At position of reestablished corner as described above and shown on accompanying Survey Map, set a 2 1/2" brass cap (marked as shown in "Monument Marking Detail"), on a 1 1/4" x 30" galvanized iron pipe 40" in the ground. Top of brass cap is 10" below road surface.

New accessories to corner monument:

A 3/4" brass washer stamped "PLS 1106" nailed 1 foot above ground level in Pacific Power and Light pole #349002 bears N 11° W, 136.7 feet.
A 3/4" brass washer stamped "PLS 1106" nailed 1 foot above ground level in Pacific Power and Light guy pole #349003 bears N 05° E, 134.7 feet.
A 5/8" x 24" iron rebar with yellow plastic cap marked "OR PLS 1106 WA PLS 17372" with top 1" above ground level in East drainage ditch of Kupers Road. bears S 29° E, 75.5 feet.
A 5/8" x 24" iron rebar with yellow plastic cap marked "OR PLS 1106 WA PLS 17372" with top 1" above ground level in East drainage ditch of Kupers Road. bears S 25° E, 129.9 feet.
Attached bearing object signs to power pole and iron rebar accessories. Set steel fence post with witness sign attached, Northeast, 25 feet from corner monument.

LOCATION AND COMMENTS: Corner falls 6 feet East of West edge of Kupers road.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla

RECEIVED BY
Surveyor's Seal
Umatilla County Surveyor
Date 4-04
Rec'd By KK
No. 04-76-B

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04