

OREGON CORNER RESTORATION FORM

CORNER NO: N-9

Section 21 Township 5N Range 34E

MAP REFERENCE: PARTITION
PLAT 1990-10

County UMATILLA Date 10-25-90

CORNER DESIGNATION

TSN R 34E
517 | 516
520 | 521

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. GLO RECORD BY ODELL & LEWIS, CONTRACT NO. 110, DATED FEB. 7, 1965. "POST, CHARGED STAKE & PITS".
RE-ESTABLISHED BY LS 346, IN 1961, MAP Q-783-C.

Monument(s) & Accessories Found: (Condition and Source)

NONE: CORNER POINT FALLS AT THE EDGE OF A GRADED ROAD. THE AREA HAS RECENTLY BEEN DISTURBED BY EQUIPMENT IN LEVELING THE AREA ADJACENT TO THE ROAD.

Monument Detail

SET 2 1/2" BRASS CAP ON 1 1/4" X 30" GALV. IRON PIPE WITH TOP OF CAP 12" BELOW ROAD. SET STEEL FENCE POST 4.0' SOUTH OF CORNER WITH WITNESS CORNER SIGN ATTACHED.

Sketch
CAP MARKED:



Monument Set (Procedures and Description)

CORNER POINT WAS RE-ESTABLISHED BY EXTENDING WESTERLY A PROPORTIONAL DISTANCE FROM THE RECOVERED NORTHEAST CORNER OF SECTION 21, THROUGH THE RECOVERED NORTH 1/4 CORNER OF SECTION 21 AND ON TO THE NORTHWEST CORNER OF SECTION 21. THE PROPORTIONAL FACTOR WAS DETERMINED BY AVERAGING THE HARRIS RECORD VERSUS THE OBSERVED DISTANCES BETWEEN THE NORTHEAST AND SOUTHEAST CORNERS OF SECTION 21, AND BETWEEN THE SOUTHEAST AND SOUTH 1/4 CORNER OF SECTION 21. SEE UMATILLA COUNTY PARTITION PLAT NO. 1990-10.

New Accessories

THE BASE OF A USGS WITNESS POST BEARS N27°E 37.7'. MEASURE TO BASE AT GROUND LEVEL.
A DOUBLE HEADED NAIL IN THE SOUTH SIDE OF PP&L POLE NO. 160000, 18" ABOVE GROUND, BEARS N86°E - 143.7'
THE BASE OF A "BURIED UNDERGROUND CABLE" SIGN POST BEARS S36°E - 81.1'. MEASURE TO BASE OF POST AT GROUND LEVEL.
A DOUBLE HEADED NAIL IN THE WEST SIDE OF PP&L POLE 209900, 18" ABOVE GROUND, BEARS S14°W - 171.1'.
PLACED "BEARING OBJECT" SIGNS ON EACH OF THE POWER POLES.

Location & Comments

CORNER LOCATED NEAR Compass Declination 19°
3 WAY ROAD INTERSECTION Firm/Agency WILLIAM R.
ON THE SOUTH SIDE OF WELLS, PLS
THE ROAD GOING WEST. Address P.O. Box 1696

Surveyor's Seal

RECEIVED BY

Umatilla County Surveyor

Date

Rec'd By JA

No. 91-18-B

PENDLETON, OR 97801

Party Chief BILL WELLS

Notes

Witness BILL QUAMPTS

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106