

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/30/05

CORNER DESIGNATION: 5N35, G-09, The East Quarter Corner of Section 8.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

In 1887, J.C. Arnold, recovered the original corner point and remonuments it with a 16 x 10 x 5 1/2" stone. This work was done under Record of Private Surveys, Survey No. 27.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1/4
S8|S9
2005
PLS 1106

MONUMENT SET:

I held a old fence intersection with fences North, West and East as best remaining evidence of original corner. I made an extensive search for the stone established by J.C. Arnold, but did not recover it. At the re-established corner point, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap 2" above ground level. Note: The wire is gone and most posts are down on the fences extending East and North. Cap marked as shown in Monument Marking Detail.

New accessories:

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap 1" above ground level bears North 52 1/2° East, 29.9 feet.

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap 1" above ground level bears South 19 1/2° East, 32.1 feet.

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap 1" above ground level bears South 50° West, 30.9 feet.

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap 1" above ground level bear North 23 1/2° West, 28.4 feet.

Wired bearing object signs to all rebar accessories. Attached "witness" sign to steel fence post 1 foot North of corner monument.

LOCATION AND COMMENTS: Corner is located on a hillside sloping West at an old fence intersection.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 829980.46

E = 8722369.67

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

/5N35G09



William R. Wells



Renews 6/30/06

05-112-C