

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/01/05

CORNER DESIGNATION: 5N35, J-05, The Northeast Corner of Section 18.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 7, 8, 17, 16. Drove charred stake; dug pits & raised mound, as per instructions.

The corner was declared lost and was re-established by J.W. Kimbrell in Record of Private Surveys, Survey No. 125. Kimbrell's notes state: "set stone 22 x 10 x 6 for cor. secs 17 & 18 19 & 20".

MONUMENT AND ACCESSORIES FOUND:

None. Corner area falls in a "rock field" in a North-South fence line. Many of the stones in the corner area have been placed in rock cribs or wire barrels to support the fence. There is no evidence of fences or field lines extending into the corner area from the East or West.

MONUMENT MARKING DETAIL:

T5N R35E
S7|S8
S18|S17
2005
PLS 1106

MONUMENT SET:

I re-established this corner position perpendicular to the midpoint of a line between the West 1/4 corners of Sections 8 and 17, holding the existing North-South fence line for departure. At re-established corner position, set a 5/8" x 16" rebar driven to bedrock, with 2" aluminum cap. The aluminum cap is 4" above ground level. Cap marked as shown in Monument Marking Detail.

New accessories:

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap 1" above ground level bears North 01° East, 27.1 feet.

"XBO" chiseled in the top of a 24"x24"x18" (exposed area) immovable rock bears North 47° East, 30.2 feet. Measured to "X".

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap 1" above ground level bears South 45° East, 22.0 feet.

"X" chiseled in East face of a rock out crop, 6" above the ground line bears North 45° West, 1.6 feet.

Attached bearing object signs to rebar accessories. Nailed "witness" sign to wood fence post 6 1/2' North of corner monument.

LOCATION AND COMMENTS: Corner is located in a "rock field", in a North-South fence line.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 827178.29
E = 8717328.64

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/5N35J05

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06

05-112-C