

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/08/05

CORNER DESIGNATION: 5N35, N-15, The South Quarter Corner of Section 15.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits; raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1 S15
4 S22
2005
PLS 1106

MONUMENT SET:

Held a fence angle in a old fence running North and South as best remaining evidence of original corner. There is also a field line approaching from the East. A re-established corner position, set a 2 1/2" brass cap on 2 1/2" by 30" galvanized iron pipe, 30" in the ground, marked as shown in Monument Marking Detail. Monument is set just west of fence post at fence angle point.

New accessories:

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", cap 1" above ground level in fence bears North 05° East, 54.4 feet.

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", cap 1" above ground level in fence bears North 05° East, 28.5 feet.

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", cap 1" above ground level in fence bears South, 25.3 feet.

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", cap 1" above ground level in fence bears South, 46.8 feet.

Attached bearing object signs to rebar accessories. Attached "witness" sign to wood fence post 0.5 feet East of corner monument.

LOCATION AND COMMENTS: Corner is at a fence angle point in North-South fence. A field line approaches from the East.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 822193.29

E = 8730513.66


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35N15



William R. Wells



Renews 6/30/06