

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/20/05

CORNER DESIGNATION: 5N35, N-17, The Northeast corner of Section 22.

## PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 14, 15, 22 & 23; drove charred stake; dug pits & raised mound, as per instructions.

The corner was recovered on Record of Private Surveys, Survey No. 4. On Survey No. 5, the corner was not recovered. On Survey No. 16, in 1882, surveyor A.L. Coffey found "sec. post on hillside". In 1900, J.W. Kimbrell re-established the corner on Survey No. 124, and "set stone 20 x 6 x 6 inches" for corner.

In 1950, Ofner finds a 4 x 4 post on Survey No. Q-808-A. Bonneville Power Administration's Milton Tap Line route maps call for a "type B 4 x 4 wood post".

## MONUMENT AND ACCESSORIES FOUND:

Found 4 x 4 inch square leaning cedar square post with visible scribing "T5N" etc. and shiner and surveyors tack in the side of post. At the South side of the post is a 20 x 13 x 6 inch unmarked stone set vertically. This would be the stone established by Kimbrell in 1900.

## MONUMENT MARKING DETAIL:

T5N R35E  
S15 | S14  
S22 | S23  
2005  
PLS 1106

## MONUMENT SET:

At the position of the recovered stone, set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe, 26" in the ground on hillside. Buried stone beside new corner monument. Cap is marked as shown in Monument Marking Detail.

## New accessories:

A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with top 4" above ground level, bears South 81° East, 23.1 feet.

A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with top 4" above ground level, bears South 05° East, 37.0 feet.

A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with top 4" above ground level, bears North 81° West, 43.0 feet.

A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with top 4" above ground level, bears North 28° West, 46.7 feet.

Attached bearing object signs to all rebar accessories. Set steel fence post 1 foot South of corner monument and attached "witness" sign.

LOCATION AND COMMENTS: Corner is located on a hillside sloping Northeast.

OREGON STATE PLANE COORDINATES, North Zone, NAD 83(91), International Feet:

N = 822307.09

E = 8733136.57


FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witness: Jason Wells, LSIT

/5N35N17

Surveyor's Seal



*William R. Wells*  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Renews 6/30/06

05-112-C