

OREGON CORNER RESTORATION FORM

Section 19

Township 5N

Range 35E

County Umatilla

Date: 01/15/10

Corner Designation: 5N35N5

Corner common to section 17,18,19,20 T5NR35E

_____	Condition Report Only
<u> X </u>	Not Found
_____	Remonumented
_____	Unrecorded
<u> X </u>	Surveyed In
<u> X </u>	Referenced Out


Previous Renewals / Surveys, etc.

Surveyed by Wm. H. Odell & Wm. S. Lewis under Contract No. 110, dated February 7th 1865.

Monuments and Accessories Found: (Condition and Source)


None.

Diagram



Sketch

Magnets are App. 14" deep.



NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N822273.86
E8717368.53
LAT - 45° 54' 15.59987" N
LON - 118° 28' 32.75308" W

Monument (s) Set (Procedures and Description)

Set a 1 1/2" Galvanized Iron pipe w/ a 2 1/2" Brass Cap Stamped as shown.
A magnet lies N 30° E, 11.40'.
A magnet lies S 87°30' E, 10.60'.
A magnet lies S 9°30' E, 8.43'.
A magnet lies N 65° W, 8.60'.

References Set:

None

Location and Comments

Cor. falls on steep Northerly slope approx. 1/3 way down from top to finger of Pine Creek.

Compass Declination
17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert Douglas English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RENEWAL DATE: 12/31/11

RECEIVED BY:

Date: 12-09
Rec'd By: _____
No. 09-176-B

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055