

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/20/05

CORNER DESIGNATION: 5N35, R-13, The Northeast corner of Section 28.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 21, 22, 27 & 28; drove charred stake; dug pits & raised mound, as per instructions.

In Record of Private Surveys, Survey No. 106, calls for the "corner to Secs 21-22-27 & 28". Survey No. 182, diagram, uses the same record dimensions as Survey No. 106. Both of these surveys were made by J.W. Kimbrell. Survey No. 182 subdivided Section 28.

MONUMENT AND ACCESSORIES FOUND: 2" diameter iron fence corner post, in a fence running East & West.

MONUMENT MARKING DETAIL:

T5N R35E
S21 | S22
S28 | S27
2005
PLS 1106

MONUMENT SET:

I accepted the 2" diameter fence corner post, in East & West fence as best remaining evidence of the original corner location. There is also a field berm extending South from this point. At the corner point, just North of 2" fence corner post, set 2 1/2" brass cap on a 2 1/2" x 30" galvanized iron pipe, 24" in the ground, marked as shown in Monument Marking Detail.

New accessories:

A 5/8" x 30" rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with top 1" above ground level in fence line bears East, 21.3 feet.

A 5/8" x 30" rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with top 1" above ground level in fence line bears East, 41.0 feet.

A 5/8" x 30" rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with top 1" above ground level in fence line bears West, 26.8 feet.

A 5/8" x 30" rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with top 1" above ground level in fence line bears West 48.6 feet.

Attached bearing object signs to all rebar accessories. Attached "witness" sign to 2" diameter fence post 0.5 feet South of brass cap monument.

LOCATION AND COMMENTS:

Corner is located in a fence running East-West. A field line extends South from this corner. North of the East-West fence is a 10 foot wide field access road along fence.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 817091.52
E = 8728483.19


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Witnesses: Jason Wells, LSIT

/5N35R13

Surveyor's Seal



William R. Wells



Renews 6/30/06

05-112-c