

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/03/05

CORNER DESIGNATION: 5N35, T-25, The East Quarter Corner of Section 25.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for 1/4 Sec.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N
R35E R36E
1/4
S25|S30
2005
PLS 1106

MONUMENT SET:

Corner was re-established by single proportion measure midway between the Southeast and Northeast corners of Section 25. The corner falls in Basket Mountain Road. A field berm extends West from the corner. At re-established corner position, set 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe with cap 12" below road surface. Cap marked as shown in Monument Marking Detail.

New accessories:

A silver deep-1 magnet, buried 20" below ground surface, in farmed field, bears North 46 1/2° East, 38.3 feet.

A purple deep-1 magnet, buried 20" below ground surface, in farmed field, bears South 48° East, 40.5 feet.

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", with cap 1" above ground level, bears South 27° West, 58.5 feet.

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", with cap 1" above ground level, bears West, 30.4 feet.

Attached bearing object signs to rebar accessories. Buried bearing object signs with deep-1 magnets. Set steel fence post with "witness" sign 1 foot South of rebar that is West of corner monument.

LOCATION AND COMMENTS: Monument is located 2 feet West of Basket Mountain Road centerline with field berm running West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 814454.02

E = 8744097.55


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35T25



William R. Wells



Renews 6/30/06

05-112-C