

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/13/05

CORNER DESIGNATION: 5N35, T-05, The West Quarter Corner of Section 29.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post, drove charred stake, dug pits and raised mound, as per instructions.

In Record of Private Surveys, Survey No. 286, J. W. Kimbrell reports surveying through the corner area but does not report finding or re-establishing this corner.

MONUMENT AND ACCESSORIES FOUND: Found 18 x 10 x 3" set stone, protruding 3" above ground line. Excavated stone and found it marked "1/4" on North face. This is an area of deep but uncultivated soil. There were no other stones in the vicinity.

MONUMENT MARKING DETAIL:

T5N R35E
1/4
S30 | S29
2005
PLS 1106

MONUMENT SET:

I accept the found stone as the corner. It is approximately 10 feet North of the down remains of a East-West fence line. The stone's origin is a mystery, but it is likely the perpetuation of the original corner position from a early unrecorded survey. J.W. Kimbrell apparently missed this corner in his Survey No. 286. At the position of the found stone, set a 5/8 by 30" rebar, capped with 2" aluminum cap stamped as shown in Monument Marking Detail, 30" in the ground. Placed corner stone, East of the new monument. Placed two other small stones by the corner monument.

New accessories:

A 5/8" x 24" rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 42 1/2° East, 28.5 feet.

A 5/8" x 24" rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 31° East, 58.8 feet.

A 5/8" x 24" rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 36 1/2° East, 28.4 feet.

A 5/8" by 24" rebar wwith yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 04° West, 32.7 feet.

Attached bearing object signs to rebar accessories. Set steel fence post 2 feet North of corner monument and attached "witness" sign.

LOCATION AND COMMENTS: On hillside facing West, about 90 feet West of old road, 25 feet East of Pine Creek and about 30 feet above Pine Creek.. About 10 feet North of fence line, visible West of Pine Creek.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 814340.67
E = 8717396.61


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/5N35T05

Surveyor's Seal



William R. Wells
OREGON
JULY 22, 1971
WILLIAM R. WELLS
1106
Renews 6/30/06

05-112-c