

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/01/05

CORNER DESIGNATION: 5N35, V-07, The South Quarter Corner of Section 29.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

Record of Private Surveys, Survey No. 106 states: "1/4 Sec. cor. at fences N, S and W".

MONUMENT AND ACCESSORIES FOUND: Railroad tie fence corner post with fences running North and West.

MONUMENT MARKING DETAIL:

T5N R35E
1/4 S29
S32
2005
PLS 1106

MONUMENT SET:

I held a railroad tie fence corner as the best remaining evidence of the original corner location and set a 2 1/2" brass cap on a 2 1/2" x 30" galvanized iron pipe, 26" in the ground. Fences run North and West from the corner. Cap is marked as shown in Monument Marking Detail.

New accessories:

- A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" in fence, with cap 1" above ground level bears North 08° East, 32.8 feet.
 - A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" in fence, with cap 1" above ground level bears North 08° East, 58.2 feet.
 - A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" in fence, with cap 1" above ground level bears North 81° West, 31.3 feet.
 - A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" in fence, with cap 1" above ground level bear North 81° West, 53.5 feet.
- Attached bearing object signs to all rebar accessories. Attached "witness" sign to railroad tie fence corner 0.3 feet North of corner monument.

LOCATION AND COMMENTS: Corner located at a railroad tie fence corner post with fences running North and West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 811684.41
E = 8719822.56



FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35NV07

Surveyor's Seal



RENEWS 6/30/06

05-112-C