

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/01/05

CORNER DESIGNATION: 5N35, V-09, The Southeast Corner of Section 29.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 28, 29, 32 & 33; drove charred stake; dug pits & raised mound, as per instructions.

In Record of Private Surveys, Survey No. 106, J.W Kimbrell recovers this corner, by verbal testimony and survey. Survey No 182 reports identical record measurements as Survey No. 106.

MONUMENT AND ACCESSORIES FOUND: Intersection of the centerline of a East-West road with field berms running North and South.

MONUMENT MARKING DETAIL:

T5N R35E
S29 | S28
S32 | S33
2005
PLS 1106

MONUMENT SET:

I held the centerline of East-West road with field berms extending North and South as best remaining evidence of the original corner location. At the re-established corner point, set a 2 1/2" brass cap on a 2 1/2" x 30" galvanized iron pipe with cap 12" below road surface, marked as shown in Monument Marking Detail.

New accessories:

A concrete nail in the top of a 4.0 foot high old concrete gate post bears North 20° East, 20.2 feet.

A concrete nail in the top of a 4.0 foot high old concrete gate post bears South 21° East, 24.1 feet.

A blue deep-1 magnet buried 20" below ground level bears South 46° West, 47.4 feet.

An orange deep-1 magnet buried 20" below ground level bears North 54° West, 64.8 feet.

Buried bearing object signs with deep-1 magnets. Set steel fence post with "witness" sign 1 foot South of Northerly old concrete gate post.

LOCATION AND COMMENTS: Corner is at a point in the centerline of a East-West road with a field berms running North and South.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 811710.13
E = 8722464.45


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35NV09



William R. Wells



Renews 6/30/06

05-112-C