

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/27/05

CORNER DESIGNATION: 5N35, Z-07, The Standard South Quarter Corner of Section 32.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for 1/4 Sec.; drove charred stake; dug pits & raised mound, as per instructions.

In Record of Private Surveys, a unnumbered survey in Book 1, pages 133 & 134, Peter Zahner surveys through the corner but does not recover it.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

SC
T5N R35E
1/4 S32
2005
PLS 1106

MONUMENT SET:

Re-established corner position by single proportion measurement between the Southwest corner of Section 31 and the Standard South one-quarter corner of Section 33. The East-West road centerline was held for latitude at the corner common to Secs. 32 and 33. See Survey No. 02-021-C for additional information. Corner falls in wheat field. At re-established corner position, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with the top 20" below ground in wheat field, cap marked as shown in Monument Marking Detail.

New accessories:

- A silver deep-1 magnet buried 24" in ground bears North 56° East, 39.2 feet.
 - A purple deep-1 magnet buried 24" in ground bears South 49° East, 43.0 feet.
 - A blue deep-1 magnet buried 24" in ground bears South 54° West, 42.0 feet.
 - An orange deep-1 magnet buried 24" in ground bears North 45° West, 48.6 feet.
- Buried bearing object signs with deep-1 magnets.

LOCATION AND COMMENTS: Located in a actively farmed field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 806364.00
E = 8720562.79

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35NZ07



Renews 6/30/06