

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 06/02/2014

CORNER DESIGNATION: Z-19, Quarter Corner for Section 35, Township 6 North, Range 37E, and Section 2, Township 5 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by William H. Odell and William S. Lewis, Deputy Surveyors, Contract No. 110, dated February 7, 1865. Their notes state "Set a post corner for Quarter Corner for Section 35, Township 6 North, Range 37E, and Section 2, Township 5 North, Range 37E in small groove of timber on mountain side facing the North from which:

A Willow 5 inches diameter bears S, 24 links.

A Fir 10 inches diameter bears N84°E, 39 links distance.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

 T6N
¼ $\frac{S35}{S2}$ R37E
 2014 T5N
 LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 1½" x 30" galvanized iron pipe with a 2½" brass cap, 7" above ground stamped as shown, Quarter Corner for Section 35, Township 6 North, Range 37E, and Section 2, Township 5 North, Range 37E, from which:

Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N76°W, 15.05 feet.

Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N47°E, 30.21 feet.

Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S68°E, 21.13 feet.

Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S18°W, 12.53 feet.

LOCATION AND COMMENTS:

Moderate slope facing north, lightly wooded, heavy underbrush. Monument is +/- 345 feet from spur road off of Saddle Mountain Road. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 840708.22

E = 8798651.73

COMPASS DECLINATION: 15° East


SURVEYORS' SEAL:

FIRM: HDJ Design Group
 5 N. Colville, Suite 200
 Walla Walla WA 99362

WITNESSES: Thomas J. Boshart
 Felipe G. Hernandez



Greg E. Flowers



RENEWS 12/31/15

06/29/2015