

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

One-quarter corner common to Section 36, Township 6 North, Range 37 East, and Section 1, Township 5 North, Range 37 East, all in the Willamette Meridian, Umatilla County, Oregon.

A-23

History of original corner establishment:

G.L.O. William H. Odell and William S. Lewis, Deputy Surveyors, Contract No. 110, dated 07 February, 1865.

"Set 1/4 Section post corner from which: A Fir 20 in. dia., bears S54°30'E 20 lks. dist. A Willow 5 in. dia., bears N18°W 30 lks. dist."

Description of evidence found:

Bert W. Udell, Sept. 11, 1956: "I have had occasion to locate and re-witness the following corner in T 6 N, Range 37 East, W.M., in Umatilla County:

- S 1/4 Cor., Section 36, T 6 N, R 37 E: 20" Fir S54 E 13.2 ft. Now dead--29". We cut out to scribe. 5" Willow N 9W 19.8 ft. Old stub, no proof. I scribed 16" Fir on North side for 1/4 corner "1/4" "1/4" and witnessed it by scribing. 10" Fir N 6 W 15.8 ft. "1/4S" "BT". signed: Howard E. Taylor"

Gregory A. Crites, Registered Professional Land Surveyor, Ore. No. 1887 & Paul W.P. Tomkins, Registered Professional Land Surveyor, Ore. No. 2360, July 6, 1992.

"We found the 16" dia. Fir marked for 1/4 corner by Udell lying on the ground with marks plainly evident. A "Walla Walla Lumber Company" Yellow Metal Location Poster is affixed to this tree.

The 10" dia. Grand Fir, N6°W, 15.8 ft. established by Udell is now 25" in dia. with face completely overgrown. I opened the tree to expose the face and found scribing "1/4S" on the upper face plainly evident.

The original 20" dia. Fir S54°E 13.2 ft. is now a rotten stump with no marks evident."

Description of monument and accessories I established to perpetuate the original location of this corner:

At record bearing and distance from the Udell bearing tree N6°W 15.8 ft., I set a standard 1" dia. "Hoffland" galvanized iron pipe with 2-1/2" Bronze cap marked as shown, the top sticking 6 inches out of the ground, in the center of the stump remains of the 16" dia. Grand Fir Bert Udell marked for the 1/4 corner, from which:

An 11-1/2 in. dia. Engelmann Spruce bears N44°30'W, a distance of 18.25 feet to center, with face mkd. "T6NR37E1/4S36BT". I set an Aluminum nail in 3/4 in. Brass washer mkd. "WA 25843 OR 2360" driven into the center of the "B" scribed on face, which is typical for all bearing trees established in this re-witness.

An 18 in. dia. Grand Fir bears N36°15'E, a distance of 30.7 feet to center, with face mkd. "T6NR37E1/4S36BT".


A 22-1/2 in. dia. Grand Fir bears S72°30'E, a distance of 39.2 feet to center, with face mkd. "T5NR37E1/4S1BT".

A 15 in. dia. Grand Fir bears S35°30'E, a distance of 27.6 feet to center, with face mkd. "T5NR37E1/4S1BT".

A 6.0 ft. studded "T" steel fence post driven 1.5 feet into the ground bears North, a distance of 1.0 feet.

I affixed Umatilla County Surveyor Yellow Metal Bearing Object signs to all bearing trees. I also affixed Yellow Metal Bearing Tree signs (penalty for disturbance, etc.) to each tree.

Bearings are magnetic using a "Silva Ranger" compass, with a declination of 19°E calibrated to true bearing by Solar observation.



REGISTERED PROFESSIONAL LAND SURVEYOR

Paul W.P. Tomkins

OREGON JULY 26, 1988 PAUL W.P. TOMKINS 2360

8/26/92

Office of \_\_\_\_\_ County of \_\_\_\_\_ State of \_\_\_\_\_, I hereby certify that the within instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_. (COUNTY OFFICIAL) by \_\_\_\_\_ (DEPUTY)

RECEIVED BY

Umatilla County Surveyor Date 9-92 Rec'd By [Signature] No. 92-106-C