

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

One-quarter corner common to Sections 1 & 2,
One-quarter Corner common to Sections 1 & 2, Township 5 North, Range 57 East, of the Willamette Meridian,
Umatilla County, Oregon.

C-21

History of original corner establishment:

GLO:
George Williams, Deputy Surveyor, Contract No. 176,
20 July, 1872.
"Set post for 1/4 Sec. Cor. from which:
A Willow, 5 in. dia. bears N18°W 31 lks. dist.
A Fir, 18 in. dia. bears S14°E 42 lks. dist."

Description of evidence found:

A diligent search for this monument was performed. I could find no trace of the original monument or its accessories. I consider this corner to be lost and re-established its position at the single proportionate position computed holding the Northwest and Southwest corners of Section 1 to control.



REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 26, 1988
PAUL W.P. TOMKINS
2360

8/26/92

Description of monument and accessories I established to perpetuate the original location of this corner:

At the single proportioned position noted above, I set a standard 1" dia. "Hotpland" galvanized iron pipe with 2-1/2" Bronze cap marked as shown, top flush with the surface of the ground, from which:

An 8 in. dia. Western Larch bears N11°45'N, a distance of 13.6 feet to center, with face mkd. "1/4S2BT". I set an Aluminum nail in 3/4" Brass washer mkd. "WA 25893 OR 2360" in the center of the "B" scribed on the face, which is typical for all bearing trees established at this corner.

A 40 in. dia. Western Larch which has been hit by lightning with the top broken out and the east half blown away bears N14°30'E, a distance of 61.9 feet to center, with face mkd. "1/4S1BT".

An 11 in. dia. Western Larch bears N54°E, a distance of 4.6 feet to center, with face mkd. "1/4S1BT".

A 9 in. dia. Western Larch bears S54°15'W, a distance of 10.1 feet to center, with face mkd. "1/4S2BT".

I affixed Umatilla County Surveyor Yellow Metal Bearing Object signs to each bearing tree. I also affixed Yellow Metal Bearing Tree signs (penalty for disturbance, etc.) to each tree.

Bearings are magnetic using a "Silva Ranger" compass, with a declination of 19°E calibrated to true bearing by Solar observation.

RECEIVED BY

Umatilla County Surveyor

Date 9-92

Rec'd By [Signature]

No. 92-106-C

Office of _____ County of _____
State of _____, I hereby certify that the within instrument was
filed in this office for record on the _____ day of _____, 19____.

(COUNTY OFFICIAL) by _____ (DEPUTY)