

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

One-quarter corner common to Section 1,  
Township 5 North, Range 37 East,  
and Section 6, Township 5 North, Range 38 East,  
all in the Willamette Meridian, Umatilla County, Oregon.

C-25

History of original corner establishment:

George Williams, Deputy Surveyor, Contract No. 172, July 20, 1872

"Set post for 1/4 Sec. Cor. from which:

A White Fir, 12 in. dia. bears S 50° E 21 lks.

A White Fir, 6 in. dia. bears N 80° W 71 lks. dist.

Description of evidence found:

Proportioned position falls immediately east of a grove of large old Grand Fir (300+ years). We found evidence of axe marks and old faces on two living trees which were marked in the 1870's based upon counts of the annual rings. I dissected 8 of these old trees in the vicinity of the proportioned position at the quadrants given on the original notes, but found no evidence of original scribing. After careful analysis it was found that the large old trees were too large to have been marked as the original bearing trees in 1872. I consider this corner to be lost.

Description of monument and accessories I established to perpetuate the original location of this corner:



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Paul W.P. Tomkins*

OREGON  
JULY 26, 1988  
PAUL W.P. TOMKINS  
2360

8/26/92

At the single proportioned position between the monuments established at the northeast and southeast corners of Section 1, I set a 1" standard "Hoffland" galvanized iron pipe with 2-1/2" Bronze cap mkd. as shown on the accompanying detail, from which:

A 21 in. dia. Grand Fir bears N57°30'W, a distance of 7.55 feet to center, with face mkd. "T5NR37E1/4S1BT". An asphalt nail driven in 3/4" Brass washer mkd. "PLS 2360" is set in center of "B" on face.

An 18 in. dia. Grand Fir bears N51°30'E, a distance of 16.54 feet to center, with face mkd. "T5NR38E1/4S6BT". An asphalt nail driven in 3/4" Brass washer mkd. "PLS 2360" is set in center of "B" on face.

A 19 in. dia. Douglas Fir bears S17°E, a distance of 42.86 feet to center, with face mkd. "T5NR38E1/4S6BT". An asphalt nail driven in 3/4" Brass washer mkd. "PLS 2360" is set in center of "B" on face.

A 16 in. dia. Douglas Fir bears S52°W, a distance of 49.64 feet to center, with face mkd. "T5NR37E1/4S1BT". An asphalt nail driven in 3/4" Brass washer mkd. "PLS 2360" is set in center of "B" on face.

I affixed Umatilla County Surveyor Yellow Metal Bearing Object signs to these Bearing Trees. I also affixed Bearing Tree signs (penalty for disturbance, etc.) to each tree.

Bearings are true, based upon Solar Observation by the "Hour Angle Method" taken at Latitude 45°56'39.5" North and Longitude 118°07'11.6" West.

Office of \_\_\_\_\_ County of \_\_\_\_\_  
State of \_\_\_\_\_, I hereby certify that the within instrument was  
filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_ Date  
\_\_\_\_\_ by \_\_\_\_\_  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 9-92

Rec'd By AK

No. 92-106-C