

OREGON CORNER RESTORATION FORM

Section: 12  
Township: 5N  
Range: 37 EWM  
County: Umatilla  
Date: 10/06/94  
Corner Designation: H-23

Previous Renewals/Surveys, etc.: None

Monument(s) & Accessories Found (Condition & Source): None

Monument Detail: TOMKINS SURVEYING

T5N R37E  
C-S 1/16  
+  
S12  
1994  
WA 25893 OR 2360

Monument Set (Procedures & Description):

We ran a traverse North from the South Quarter of Section 12 to the Center Quarter of Section 12. Then we traversed from the Center-South 1/16 to the South 1/16 of Section 11 and Section 12, then North to the West Quarter of Section 12. Closure exceeded 1 in 5000. We previously broke down Section 12 as shown on Survey No. 92-106-C. A 2 inch aluminum cap on a 5/8" x 30" rebar was set at the corner position.

New Accessories:

A steel fence post with a land survey monument sign was placed alongside.  
A 11" tamarack bears North 83° West, 41.3 feet marked "1/16 bt"  
A 8" white fir bears South 56° East, 16.2 feet marked "1/16 bt"

Location & Comments:


The corner falls on the North side of a noll.

Compass Declination:

19° East

Surveyor's Seal


Firm/Agency: Paul Tomkins Land Surveying  
6 1/2 N 2nd  
Walla Walla WA 99362



Party Chief: Thomas S. Butler

*Paul W. P. Tomkins*

Notes: Thomas S. Butler



Witness: Merle Sherman

renews 12/31/94  
10/18/94

RECEIVED BY

Umatilla County Surveyor

Date 10-94

Rec'd By KR

No. 94-151-R