


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: In 1872, under GLO Contract No. 176, George Williams set post for cor to secs 4,5,32 and 33 from which a Willow 5 ins. dia bears S41<sup>0</sup>W, 18 lks dist. A White Fir 18 ins dia. bears N60<sup>0</sup>W, 38 lks dist. A White Fir 26 ins dia. bears S65<sup>0</sup>W, 13 lks. dist. A Spruce 7 ins. dia. bears N22<sup>0</sup>E, 36 lks dist.

Index File No. A-9



Description of corner evidence found: At cor location found 3/4" pin and part of original post beside pin. Found rotted remains of S.E. BT with pieces of blaze and visible scribing "BT". Found root holes for location of BT. Found rotted stump and down rotted N.W. BT with visible scribing "S32 BT". Found down rotted NE BT with visible scribing "S33 BT". Pit fits record bearings and distances from BTs.

Description of monument and accessories I established to perpetuate the original location of this corner: In place of found pin set 1"x30" pipe with 3" brass cap attached stamped set pipe 22" in ground with mound of dirt to cap.

Bearing Trees:

A White Fir 15" dia bears N71<sup>0</sup>W, 52.0 ft scribed T6N R38E S32 BT.  
 A Spruce 6" dia bears N37<sup>0</sup>E, 23.3 ft scribed T6N R38E S33 BT.  
 A Tamarack 12" dia bears S27<sup>0</sup>E, 26.7 ft scribed T5N R38E S4 BT.  
 A White Fir 10" dia bears S2<sup>0</sup>W, 14.5 ft scribed T5N R38E S5 BT.

Attached 54-3 and 54-4 signs to new BT's. Painted blazes and 6" band around new BT's. Attached brass washer stamped LS 1294 to foot blaze of new BT's.

CROWN ZELLERBACH  
 T6N R38E  

S32	S33
S5	S4
T5N	

 1980  
 OR PLS 1294



I hereby certify the above corner monument was established as herein described on Sept. 4, 1980.

Witnesses: R. Orton  
 L. Huntsman

Office of.....County Surveyor..... County of..... Umatilla  
 Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of..... December....., 1980  
 David Grumbey by Betty Shatto  
 (COUNTY OFFICIAL) (DEPUTY)