


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. C-7

History of original corner establishment:

No corner was originally set.



Description of corner evidence found:

Description of monument and accessories | established to perpetuate the original location of this corner:

At surveyed point set 1"x30" Galvanized Pipe with 3" brass cap stamped:


Set pipe 25" in ground. No stones available for mound.

New BTs:

A White Fir, 10" dia. bears N35⁰W, 28.0 ft., scribed C 1/4 S5 BT.

A Blue Spruce 8" dia. bears S75⁰W, 10.9 ft., scribed C 1/4 S5 BT.

Attached 54-3 and 54-9 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.



I hereby certify the above corner monument was established as herein described on October 23, 1980.

Witnesses: R. Orton
A. Hanley

Office of..... County Surveyor..... County of..... Umatilla
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... December..... 1980
Daved Krumbein..... by..... *Betty Skatts*
 (COUNTY OFFICIAL)..... (DEPUTY)