

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Section corner common to Sections 1 and 12,  
Township 5 North, Range 37 East,  
and Sections 6 and 7,  
Township 5 North, Range 38 East,  
all in the Willamette Meridian, Clatsop County, Oregon

E-25

History of original corner establishment:

George Williams, Deputy Surveyor, Contract No. 172, 20 July, 1872.

"Set post in edge of prairie, Cor. for Secs. 1, 6, 7, & 12  
from which:


- A White Fir 8 in. dia. bears S78°W 52 lks.
- A White Fir 6 in. dia. bears N85°W 40 lks.
- no other trees convenient".

George Williams, Deputy Surveyor, Contract No. 176, 20 July, 1872.

"Intersect W boundary of Twn. 34 lks. N of the Cor for Secs.  
1, 6, 7 & 12"...

Description of evidence found:

I could find no trace of the original bearing trees, but  
found an intersection of very old north/south and east/west  
barbed wire fences which match the GLO call for lying on the  
westerly edge of the "prairie" (Little Meadows). Remnants of  
the barbed wire along the north/south fence line were grown  
into the center of stumps over ninety years old. We also  
found a 36" dia. Douglas Fir stump with an overgrown burnt  
face lying southeast of this intersection. This chopped out  
face matches axe work we found at the northeast corner and  
east one-quarter of section 1. I accepted this fence inter-  
section as the best evidence of the position of the corner  
common to Sections 1, 6, 7 & 12.



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Paul W.P. Tomkins*

OREGON  
JULY 26, 1988  
PAUL W.P. TOMKINS  
2360

Description of monument and accessories I established to perpetuate <sup>8/24/92</sup>  
the original location of this corner:

I set a 1" standard "Hoffland" galvanized iron pipe with  
2-1/2" Bronze cap marked as shown on the accompanying detail,  
from which:

A 14" dia. Western Larch bears S49°W, a distance of  
72.00 feet to center, with face mkd. "T5NR37ES12BT". An  
Aluminum nail is set in a 3/4" Brass washer mkd. "PLS  
2360" in the center of "B" marked on face (typical for  
all Bearing Trees).

A 10" dia. Western Larch (forked) bears N87°W, a  
distance of 62.35 feet to center, with face mkd.  
"T5NR37ES1BT".

A 28" dia. Grand Fir bears N38°E, a distance of 69.60  
feet to center, with face mkd. "T5NR38ES6BT".

A 34" dia. Engelmann Spruce at the westerly edge of Little  
Meadows bears S63°E, a distance of 117.5 feet to  
center, with face mkd. "T5NR38ESTBT".

I affixed Umatilla County Surveyor Yellow Metal Bearing  
Object signs to these 4 bearing trees. I also affixed  
Bearing Tree signs (penalty for disturbance, etc.) to  
each tree.

Bearings are magnetic using a "Silva Ranger" compass  
with a declination of 19°E, calibrated to true bearing  
from solar observation.

Office of \_\_\_\_\_ County of \_\_\_\_\_  
State of \_\_\_\_\_, I hereby certify that the within instrument was  
filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_.

(COUNTY OFFICIAL) by (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 9-92

Rec'd by KK

No. 92-106-C