


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. E-11

History of original corner establishment: In August 1899, under GLO Contract No. 699, William E. Campbell set basalt stone 15"x10"x10" ins. 6 ins. in the ground, place mound of stone firmly about corner, for 1/4 sec cor. marked 1/4 on N. face from which a Fir 17" dia. bears N19°E 53 lks dist. marked 1/4 S4BT. A Fir 14" dia. bears S53 1/2°W, 88 lks dist. marked 1/4 S9 BT.




Description of corner evidence found: A corner location found 12"x10"x10" stone lying on the ground in mound of stone with "1/4" visible on North face. Could find no trace of original BT's.

Description of monument and accessories I established to perpetuate the original location of this corner: In place of stone set 1"x30" galvanized pipe with 3" brass cap stamped:

Set pipe 22" in ground with original stone buried alongside and mound of stone to cap.

Bearing trees:

A White Fir 9" dia bears N42°W, 52.0 ft. scribed 1/4 S4 BT
 A White Fir 8" dia bears S74°W, 57.3 ft. scribed 1/4 S9 BT



Attached 54-3 and 54-4 signs to both BT's. Attached brass washer stamped LS 1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's red.



I hereby certify the above corner monument was re-established as herein described on Sept. 10, 1980.

Witnesses: R. Orton
 M. Wagoner

Office of.....County Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the.....day of.....December....., 19.....80.....
 David Krummlein by Betty Shatto
 (COUNTY OFFICIAL) (DEPUTY)