


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. E-6

History of original corner establishment:

No corner was originally set.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 1" x 30" galvanized pipe with 3" brass cap stamped :


Set pipe 25" in ground. No stones available for mound.

New BT's:

A White Fir 14" in diameter bears S41°E, 27.7 ft. scribed W 1/16 S8 BT

A White Fir 6" in diameter bears N62°E, 6.0 ft. scribed W 1/16 S5 BT.

Attached 54-3 and 54-9 signs to both BT's. Attached brass washer stamped LS 1294 to foot blaze of both BT's Painted blazes and 6" band around both BT's Red.



I hereby certify the above corner monument was established as herein described on October 22, 1980.

Witnesses: R. Orton  
A. Hanley



Office of..... County Surveyor..... County of..... Umatilla.....  
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of..... December..... 1980.....  
*David K. Reimann* by *Betty Laatto*  
 (COUNTY OFFICIAL) (DEPUTY)