


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. E-7

History of original corner establishment: In 1872, under GLO Contract No. 176, George Williams set a Fir post for 1/4 sec from which:
 A 10" Tamarack bears N10°W 30 lks dist.
 A 15" Fir bears S52°W 4 lks. dist.



Description of corner evidence found: Remains of original SW bearing tree, now a 36" Doug. Fir stump with a notch cut on top of the stump at the correct original dia to a possible old face, no markings found. This stump is badly rotted. We open further and find no additional evidence. Note: The letters "BT" had been scribed on top of the cut area of the stump.

Description of monument and accessories established to perpetuate the

original location of this corner: Set a 1"x30" galvanized pipe with a 3" brass cap stamped:

Set pipe 20" in ground with mound of stone to cap.

Bearing trees:

A White Fir 4" dia bears S59°E 25.4 ft bark scribed 1/4 S8 blaze scribed BT.

A White Fir 12" dia bears N50°E 60.7 ft scribed 1/4 S5 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washers stamped LS 1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's red.



I hereby certify the above corner monument was re-established as herein described on Oct. 9, 1980.

Witnesses: R. Orton
 G. Wagoner
 M. Wyatt
 A. Hanley

Office of..... County Surveyor..... County of..... Umatilla
 Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... December....., 1980
 David Krumborn by..... Betty Skatto
 (COUNTY OFFICIAL) (DEPUTY)