


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. E-9a

History of original corner establishment: In 1872, under G.L.O. Contract No. 176, George Williams set post for cor to secs 4,5,8 & 9 from which a White Fir 24" dia. bears N15° W 23 lks dist. White Fir 6" dia. bears N80° E, 21 lks dist. White Fir 18" dia. bears S34°E 30 lks dist. White Fir 10" dia. bears S75°W 42 lks dist.



In 1899 a resurvey was performed by George R. & William E. Campbell under G.L.O. Contract No. 699. They found post missing and only the stumps of the bearing trees remaining. They re-established the corner common to 2 sections only by setting a basalt stone 15x12x10 ins. in ground for cor. to secs. 5 & 8 marked with 1 notch on north edge from which a Fir 16" dia. bears S74°W 75 lks. dist. marked T5N R38E S8 BT. A Fir 14" dia. bears N32½°W 69 lks. dist. marked T5N R38E S5 BT. They destroyed the marks on the stumps of the witness trees before mentioned.



Description of corner evidence found: At corner location found a White Fir live 30" dia. with opened blaze and visible scribing "8", could find no evidence of original stone, or other BT or stumps. The found BT is N.W. B.T.

Description of monument and accessories established to perpetuate the

original location of this corner: At record bearing and dist. from found BT set 1"x30" galvanized pipe with 3" brass cap stamped:

Set pipe 20" in ground with mound of stone to cap. From which:
 A White Fir 10" dia. bears S29°W 14.4 ft. scribed: T5N R38E S8 BT
 A White Fir 12" dia. bears N80°W 69.7 ft. scribed: T5N R38E S5 BT

Attached 54-3 and 54-4 signs to all BT's painted blazes and 6" band around all BT's red. Attached brass washer stamped LS 1294 to foot blaze of new BT's.



I hereby certify the above corner monument was re-established as herein described on Sept. 12, 1980

Witnesses: R. Orton
 M. Wagoner

Office of..... County Surveyor..... County of..... Umatilla
 Oregon
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... (December)..... 1980
 David H. Humber (COUNTY OFFICIAL) by Betty Shatto (DEPUTY)