


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. H-6

History of original corner establishment:

No corner was originally set.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 1"x30" Galvanized Pipe with 3" brass cap stamped:

Set pipe 24" in ground with mound of dirt to cap.

From which:

A Spruce 10" dia. bears N36°E 80.4 ft., scribed: SW 1/16 S8 BT.

A Lodge Pole Pine 10" dia. bears S3°E 144.9 ft., scribed: SW 1/16 S8 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washers stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs. red.



I hereby certify the above corner monument was established as herein described on November 5, 1980.

Witnesses: R. Orton
G. Wagoner
Mike Wagoner

Office of..... County Surveyor County of..... Umatilla
Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of..... December..... 19..... 80
..... *Daniel Krumbein* by *Betty Shatto*
(COUNTY OFFICIAL) (DEPUTY)