


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. H-9b

History of original corner establishment:

No corner was originally set.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 1"x30" Galvanized Pipe with 3" brass cap stamped:

From which:

A White Fir 14" dia. bears N60°E 61.8 ft., scribed: S 1/16 S9 BT.

A White Fir 7" dia. bears S26°E 64.9 ft., scribed S 1/16 S9 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.



I hereby certify the above corner monument was established as herein described on September 26, 1980.

Witnesses: R. Orton  
G. Wagoner  
L. Huntsman  
A. Hanley

Office of..... County Surveyor..... County of..... Umatilla  
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of..... *December*....., 19..... *80*  
*David Krumborn*..... by *Betty Shatto*  
 (COUNTY OFFICIAL)..... (DEPUTY)