


T. 5 N. R. 39 E.
Merid. Willamette

R.D. Pomeroy & Walla Walla
N.F. Umatilla

County Wallowa
State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From junction of 64 and 6415 travel northeasterly on 6415 approx. 0.15 miles to a small creek. Walk northerly up the creek approx. 250 feet to the Angle Point which is located in the bed of the creek.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North
X: 2698167.877 meters
Y: 248080.920 meters
Datum: NAD83(1991)

Signature

David Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/1998

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 24" rebar, with a 3 1/4" aluminum cap, 17" into the creek bed, stamped "W-T WILDERNESS AP-86 RLS 2308 1997".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

14" Subalpine Fir, S 81 1/2 W, 83.1 feet, scribed "WB/86" "BT".

16" Subalpine Fir, N 27 3/4 W, 46.5 feet, scribed "WB/86" "BT".

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By David Schlaich Title Land Surveyor Date 10/1998 State Registration No. _____
or Agency _____
Certified Corner Record Prepared? Yes No _____ Filed At: _____ Date _____

REMARKS