


T. 5 N. R. 39 E.
Merid. Willamette

R.D. Pomeroy & Walla Walla
N.F. Umatilla

County Wallowa
State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From westerly junction of 6415 and 6415-020 travel easterly on 6415-020 approx. 0.51 miles and then walk northerly approx. 230 feet to the Angle Point.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North
X: 2699590.333 meters
Y: 247874.487 meters
Datum: NAD83(1991)

Signature

David Schlaich

Title

Land Surveyor.

Division

Headquarters

S.O.

Date

10/1998

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 36" rebar, with a 3 1/4" aluminum cap, 30" in the ground, stamped "W-T WILDERNESS AP 85-49 RLS 2308 1998".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

12" Lodgepole Pine, N 18 E, 8.1 feet, scribed "WB/85-49" "BT".

17" Western Larch, S 84 1/2 E, 87.0 feet, scribed "WB/85-49" "BT".

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By David Schlaich Title Land Surveyor Date 10/1998 State Registration No.
or Agency
Certified Corner Record Prepared? Yes No Filed At: Date

REMARKS

Index File No.

T. 5 N.

R. 39 E.

M. Willamette

Tract or Survey No.

Wenaha-Tucannon
Wilderness

Cor. AP 85-49