


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

George S. Pershin under Contract No. 362
Dated August 2, 1880
Set Basalt Stone 16" X 12" X 6 from which
Pine, 36" Dia., BRS. N12°E., 28 Lks. Distance.
Fir, 9" Dia., BRS. S85°W., 5+ Lks. Distance.



Description of corner evidence found:

Found (BRGS. and DISTs from re-established corner point; original stone is now gone).
Douglas Fir, 16" Dia., BRS. S84 1/4°W., 35.6 Ft. Distance with scribing visible on open blaze.
Rotted Stump, 26" Dia., BRS. N20°E., 18.5 Ft. Distance with no scribing remaining.

Description of monument and accessories established to perpetuate the original location of this corner

Set 32" X 2" flanged iron pipe with brass cap marked:

From which new BTs

Douglas Fir, 10" Dia., BRS. N27°W., 33.6 Ft. Dist.
Marked: 1/4 S36 SC BT
Larch, 11" Dia., BRS. N15 1/2°E., 20.2 Ft. Dist.
Marked: 1/4 S36 SC BT
6' Iron Fence Post with "Attention" sign within 5' of Corner

SC
T5S R29E
1/4 S36
1979
PLS 346

All B.T. have BT tag and painted red strip. New BTs have Brass Washer stamped: PLS 346; nailed to lower blaze.

Office of.....County Surveyor..... County of.....Umatilla.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of.....
..... by.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 10-17-79
Rec'd By msj
No. A-1171-B

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Wayne O. Harris
OREGON
MAY 6, 1955
WAYNE O. HARRIS
346

GPO 796-333

Corresponding drawing