


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430.

Surveyor General Record States:

Set basalt stone 18 x 12 x 6 ins. in mound of stone, for cor. to sec'ts. 35-36-1-2, marked with 5 notches on West & 1 notch on East edges.

A 8" Pine bears N 79 W, 226 lks.
Raised mound of stone along side.



Z-21

No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found original stone, call size, properly marked in mound of stone, from which:

Original BT

A 24" Pine, poor condition, bears N78W, 148.0 ft., scribes visible.

Description of monument and accessories established to perpetuate the original location of this corner

In position of stone, I set 2½"x30" iron pipe with brass cap, marked as shown, 24" in ground, from which:

Net BTs

- A 9" Pine bears N89E, 51.9 ft. marked T4S R30E S36 BT.
- A 10" Pine bears S 7E, 307.4 ft. marked T5S R30E S 1 BT.
- A 14" Pine bears S19W, 213.2 ft. marked T5S R30E S 2 BT.
- A 12" Pine bears N61W, 160.0 ft. marked T4S R30E S35 BT.

Nailed brass washer to BT blaze.


Buried stone South and along side pipe.

Set steel fence post 5+ ft. North of corner.
Used steel tape and magnetic compass with 20° E declination.

Measured to face of blaze on original BT and center of new BTs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Duane J. Griffith
OREGON
JULY 19, 1964
DUANE J. GRIFFITH
644



Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 13 day of Aug, 1974, at o'clock m., (signed)
Keith Thompson by
(COUNTY OFFICIAL) (DEPUTY)

I-108-R