

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G-25


History of original corner establishment: Corner established in 1880 by George S. Pershin under General Land Office Contract No. 373.

Surveyor General Records States:

Set basalt stone 14 x 12 x 10 ins. for $\frac{1}{4}$ cor.

A 24" Fir bears N 38 E, 19 lks.

A 18" Tamarack bears N 52 W, 36 lks.



No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found original stone, call size, marked $\frac{1}{4}$ on W face in a mound of stone, from which:

Original BTs

A rotted fir stump bears N38E 12.5 ft., no scribes visible.

A 24" Tamarack stump bears N52W, 23.8 ft., no scribes visible.

Description of monument and accessories established to perpetuate the original location of this corner

At position of stone, I set 2 $\frac{1}{2}$ "x30" iron pipe with brass cap marked as shown, 28" in ground, from which:

New BTs

A 15" Fir bears N69E, 41.1 ft. marked $\frac{1}{4}$ S7 T5S R31E BT.

A 10" Fir bears S86W, 12.2 ft. marked $\frac{1}{4}$ S12 T5S R30E BT.

Nailed brass washer to BT blaze.

Buried stone North and along side pipe.


Set steel fence post 5+ ft. North of corner.

Used steel tape and magnetic compass with 20° E declination.

Measured to face of blaze on original BTs and center of new BTs.

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 10, 1972 DUANE L. GRIFFITH 644



Office of Surveyor County of Wasatch
 State of Utah, I hereby certify that the within instrument was filed in this office
 for record on the 13 day of April, 1974, at 4 o'clock pm, (signed)
Harold S. Thompson by Harold S. Thompson (DEPUTY)

G-25

S-63-M