

Index File No. G-5

CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____


T 55 R. 30E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Ore.

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND Found remains of Rotten wood in 3" hole with a mound of stone over hole, & 2 1/2" pole scribed 1/4 lying on the mound of stone appears to be about 20-30 years old.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND Fd. no evidence of spruce trees in the area. Since the evidence found is harmonious with surrounding found corners it's position is accepted as the 1/4 corner.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER From the Jct. of roads 5312 & 5318, go NW 3/8 mi. on rd. 5318, then go north approx. 1000' to corner.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature _____ Title _____ Division _____ Headquarters _____ Date _____

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 3"x30" galv iron pipe with 3" brass cap 20" in the ground & placed a ring of stones around pipe. stamped brass cap as shown on the diagram.

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which:

A fir 14" dia. bears N 15 E 24.4 ft. scribed 1/4 S 81 BT.

A fir 12" dia. bears N 16 W 23.8 ft. scribed 1/4 S 7 BT.

Nailed brass washers stamped PLS 848 & bearing tree signs to both trees, painted red band around tree.

Set steel posts with warning sign 5' N. (Bearing mag. comp. 20 E Dec. ~~198~~)

Work Done By D.M. Ferguson Title Surveyor Date 9-4-80 State Registration No. PLS 848
or Agency

Certified to Record? Yes No Filed At: _____ Date _____

REGISTERED
PROFESSIONAL
LAND SURVEYOR

REMARKS



OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witness to above corner.

L. Wyllie

Index File No. T. R. M. Tract or Surv. No. U.S. G.P.O. Cor. 1977-725-576/586