


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468.

Surveyor General Record States:

Set basalt stone 16 x 11 x 7 ins. for $\frac{1}{4}$ cor. Marked $\frac{1}{4}$ on W. face. From which:

- A 30" Pine bears N. 52 W., 12 lks.
- A 30" Pine bears N. 33 E., 12 lks.



Description of corner evidence found:
No record of subsequent remonumentation was found in County Records.

Found stone, call size marked $\frac{1}{4}$ from which:

Original BTs

- A 36" Pine, poor condition, bears N50W, 8.2 ft., scribes visable
- A 38" Pine, good condition, bears N32E, 8.3 ft., scribes visable.


Description of monument and accessories established to perpetuate the original location of this corner
In position of stone, I set $2\frac{1}{2}$ "x30" iron pipe with brass cap marked as shown, 24" in ground, from which:

New BT

- A 12" Pine bears S61W, 93.6 ft. marked $\frac{1}{4}$ S8 T5S R30E BT.
- Buried stone north and alongside pipe.
- Nailed brass washer to BT blaze.
- Set steel fence post $5\frac{1}{2}$ ft. South of corner.
- Used steel tape and magnetic compass with 20° E declination.
- Measured to face of blaze of original BTs and center of new BTs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Handwritten Signature
OREGON
JULY 10, 1933
DUANE J. GRIFFITH
644



Office of Surveyor County of Wasatch
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 13 day of Aug, 1974, at _____ o'clock _____ m., (signed)
Ralph Thompson by _____ (DEPUTY)
 (COUNTY OFFICIAL)

G-9

I-17R