

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


G-9

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468.

Surveyor General Record States:

Set basalt stone 16 x 11 x 7 ins. for $\frac{1}{4}$ cor. Marked $\frac{1}{4}$ on W. face. From which:

- A 30" Pine bears N. 52 W., 12 lks.
- A 30" Pine bears N. 33 E., 12 lks.



Description of corner evidence found:

No record of subsequent remonumentation was found in County Records.

Found stone, call size marked $\frac{1}{4}$ from which:

Original BTs


- A 36" Pine, poor condition, bears N50W, 8.2 ft., scribes visible
- A 38" Pine, good condition, bears N32E, 8.3 ft., scribes visible.

Description of monument and accessories established to perpetuate the original location of this corner

In position of stone, I set 2 $\frac{1}{2}$ "x30" iron pipe with brass cap marked as shown, 24" in ground, from which:

New BT

- A 12" Pine bears S61W, 93.6 ft. marked $\frac{1}{4}$ S8 T5S R30E BT.
- Buried stone north and alongside pipe.
- Nailed brass washer to BT blaze.
- Set steel fence post 5+ ft. South of corner.
- Used steel tape and magnetic compass with 20° E declination.
- Measured to face of blaze of original BTs and center of new BTs.



Office of *Surveyor* County of *Umatilla*
State of *Oregon*, I hereby certify that the within instrument was filed in this office for record on the *15* day of *April*, 19*74*, at *10* o'clock *am*, (signed) *Ralph J. Housley* by *[Signature]* (DEPUTY)

G-9