


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

H-8

① History of original corner establishment:
Corner not previously established.



② Description of corner evidence found:
N.A.

Description of monument and accessories established to perpetuate the

③ original location of this corner:
Set 3"x30" galv iron pipe with 3" brass cap stamped as shown in the diagram.
Set 26" in the ground.
From which:
A tamarack 15" dia. bears N 21 E 8.9 ft. scribed SE 1/16 S8 BT.
A lodge pole pine 8" dia. bears S 3 E 45.3 ft. " " " " "
Nailed brass washers stamped PLS 848 & bearing tree signs to each tree & painted red bands around each tree.
Set steel posts 5'N & 5'W with bdry. & warning signs.
Bearing-mag compass 20 E Dec.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witnesses to above corner.

D. Herburger
L. Wyllie

Office of... Surveyor County of... Umatilla
State of... Oregon I hereby certify that the within instrument was filed in this office
for record on the... 29 day of... January , 1981.
..... David H. Klein by
(COUNTY OFFICIAL) (DEPUTY)

S-63 M