


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-11

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468.



Surveyor General Record states:

Set basalt stone 16"x10"x9", marked ¼ on North face, from which:

- A 8" Pine bears S9W, 48 lks.
- A 10" Pine bears N79W, 76 lks.

No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found stone, call size in mound of stone marked ¼, from which:

Original BTs

A dead and down Lodge Pole Pine bears S9W, 31.7 ft., scribes visible.

The remains of a dead and down Lodge Pole Pine stump bears S79W, 50.2 ft., no scribing visible.

Description of monument and accessories established to perpetuate the original location of this corner.

In position of stone, I set 2½"x30" pipe with brass cap marked as shown, 24" in ground, from which:

New BTs.

A 14" Pine bears N61°E, 127.6 ft. marked ¼S9 T5S R30E BT.

A 14" Lodge Pole Pine bears S5°W, 32.4 ft. marked ¼S16 T5S R30E BT.

Nailed brass washer to BT blazes.

Set steel fence post 5ft. North of corner.

Buried original corner stone South and along side pipe.


Measurements taken to center of new BTs.

Corner is N20°W, 50 ft. from a small stock water pond. Used steel tape and magnetic compass with 20° E declination.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Duane J. Griffith*

OREGON  
JULY 10, 1974  
DUANE J. GRIFFITH  
644



Office of *Surveyor* County of *Wasatch*  
 State of *Utah*, I hereby certify that the within instrument was filed in this office  
 for record on the *13* day of *July*, 1974, at ..... o'clock .....m., (signed)  
*Ralph J. ...* by ..... (DEPUTY)

J-11