


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:


Corner originally established by George S. Pershin under GLO contract number 430, dated 1882. Surveyor General record states: Set a post 4 ft. long 4 ins square 24 ins in ground for cor to secs 11, 12, 13 & 14 marked T5S S12 on NE, R30E S13 on SE, S14 on SW and S11 on NW faces with 4 notches on S and 1 notch on E edges; from which:
 A pine 30 ins dia brs S38°E, 10 lks dist marked T5S R30E S13 BT.
 A pine 20 ins dia brs N69°W, 53 lks dist marked T5S R30E S11 BT.
 A pine 30 ins dia brs S18°W, 83 lks dist marked T5S R30E S14 BT.
 No tree within limits in sec 12. Dug pit 18x18x12 ins 5 1/2 ft. dist and raised mound of earth 2 ft. high 4 1/2 ft. base alongside.



Corner remonumented in 1974 by Duane I. Griffith, OPLS 644. His monumentation record states: Found 2 original BTs as follows: A 24" Pine, poor condition, bears S37°E, 6.6 ft., scribes visible. A 30" Pine, good condition, bears S16°W, 54.8 ft., scribes visible. No evidence of other BT or original stake found. At corner point, based on original BTs, I set 2 1/2"x30" iron pipe with brass cap marked (shown below), 24" in ground, from which: New BTs A 10" Pine bears N28°E, 12.2 ft. marked T5S R30E S12 BT. A 8" Pine bears S13°E, 57.7 ft. marked T5S R30E S13 BT. A 18" Pine bears N36°W, 77.1 ft., marked T5S R30E S11 BT. Set steel fence post 5+/- ft. North corner. No record of subsequent monumentation found in Umatilla County survey records.

Found 2 1/2 inch diameter brass cap monument in mound of stone, marked as shown:

Found a 13 inch diameter Ponderosa Pine N28°E, 12.2 feet, live and vigorous with scribes visible.
 Found a 10 inch diameter Ponderosa Pine S13°E, 57.7 feet, dead and down with scribes visible.
 Found a 22 inch diameter Ponderosa Pine snag S38°E, 10 lks with scribes visible.
 Found a 29 inch diameter Ponderosa Pine S16°W, 54.8 feet, live and vigorous with scribes visible.
 Found a 24 inch diameter Ponderosa Pine N36°W, 77.1 feet, live and vigorous with scribes visible.
 Found steel fencepost approximately 5 feet North with rusting attention sign attached.
 Distance to the original BTs are to the face of the blaze.
 Distance to subsequent BTs are to the center of the tree.



Description of monument and accessories I established to perpetuate the original location of this corner:

From the above described corner monument:

New BT:
 A 12 inch diameter Ponderosa Pine bears S1°E, 28.30 feet marked T5S R30E S13 BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs if not previously signed.

Attached land survey monument sign to existing fencepost North of monument.

I hereby certify that the above corner point was perpetuated as hereon described on September 2, 1988.

Witnesses: Jeff Petersen and Rick Robinson



I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office for record on the 2nd day of September 1988
David H. Kumbien by Kathleen Ambrey
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surv. per

1-13

Date 9-88
 Rec'd By SA
 No. 88-63-R

J-21

☆ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276