


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by George S. Pershin under GLO contract number 430, dated 1882. Surveyor General record states:

Set basalt stone 12x10x10 ins 8 ins in ground for 1/4 sec cor marked 1/4 on W. face; from which,

A Pine 40 ins dia brs S38°W, 63 lks dist. marked 1/4 S BT
A Pine 10 ins dia brs S41°E, 276 lks dist. marked 1/4 S BT



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found no evidence of the original corner stone.

Found a 29 inch diameter Ponderosa Pine S41°E, 276 lks live and vigorous with blaze evident. I opened and found scribing 1/4 S.

Found no evidence of the original Southwest bearing tree.

Distance to the existing BT is to the face of the blaze.

Description of monument and accessories I established to perpetuate the original location of this corner: At record bearing and distance from the found original bearing tree, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 16 inches in the ground, from which:

New BTs:
A 10 inch diameter Ponderosa Pine bears S32°E, 64.60 feet marked 1/4 S13 BT
A 13 inch diameter Ponderosa Pine bears S39°W, 70.31 feet marked 1/4 S14 BT

Raised a mound of stone around monument, 4 ft. base to top of cap.

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.
Set a steel fencepost approximately 5 feet North with property boundary and land survey monument signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on August 29, 1988.

Witness: Rick Robinson



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office for record on the 27th day of September 1988
David H. Kumbien by Kathleen Ambrose
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

1-5

RECEIVED BY
Umatilla County Surveyor
Date 9-88
Rec'd By [Signature]
No. 88-63-R

U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

L-21