

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


N-13

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468

Surveyor General Record States:

Set basalt stone 15 x 10 x 6 for Cor. to Sects. 15-16-21-22 marked with 3 notches on S & E edges, From which:

- A 30" Pine bears S 10 W, 75 lks.
- A 30" Pine bears S 20 E, 98 lks.
- A 20" Pine bears N 42 E, 134 lks.
- A 30" Pine bears N 9 W, 225 lks.



No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found original stone, call size, properly marked in mound of stone, from which:

Original. BTs

- A 30" Pine, good condition, bears N42E, 89.4 ft., scribes visable.
- A 28" Pine, good condition, bears S20E, 65.5 ft., scribes visable.
- A 28" Pine, good condition, bears S10W, 50.2 ft., blaze healed.
- A 30" Pine stump bears N9W, 151.4 ft., no scribes visable.


Description of monument and accessories established to perpetuate the original location of this corner

In place of stone, I set 2 1/2"x30" iron pipe with brass cap marked as shown, from which:

New BT

A 12" Pine bears N18W, 16.4 ft. marked T5S R30E S16 BT.

- Nailed brass washer to BT blaze.
- Buried stone North and along side pipe.
- Set steel fence post 5' North of corner.
- Used steel tape and magnetic compass with 20° E declination.
- Measured to face of blaze on original BTs and center of new BT.



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 15th day of August, 1974, at 11 o'clock am, (signed)
Ukiah Thompson by _____
 (COUNTY OFFICIAL) (DEPUTY)

N-13