


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



Description of corner evidence found:

N.A.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv iron pipe with 3" brass cap 20" in the ground. Stamped brass cap as shown in the diagram.

From which:

A fir 17" dia. bears N 4 E 11.2 ft. scribed C W W 1/64 S8 BT.

A fir 10" dia. bears S 3 W 16.3 ft. " C W W 1/64 S8 BT.

Nailed brass washers stamped PLS 848 & bearing tree signs to each tree, painted red band around each tree.

Set steel posts with warning & bdry. signs 5' N & 5' E.

Bearing mag. compas 20 E Dec.

Witness to above corner.

L. Wyllie

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1988
DOUGLAS M. FERGUSON
848

Office of Surveyor County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the 26 day of JANUARY, 1981
David H. Klein by
(COUNTY OFFICIAL) (DEPUTY)

S-63-A